

22×8 Covered Porch — 176 sq ft

O'Sullivan Construction & Property Management

Estimate / Quote

22×8 Covered Porch — 176 sq ft

Prepared for: Homeowner

Date: 2026-07-03

Description

Qty

Unit

Unit Cost

Line Total

Covered porch — materials (22×8 ft, 176 sq ft): PT framing lumber, composite decking and fascia, hidden fasteners, composite railing kits, 6×6 column wraps, roof sheathing, ice & water shield, synthetic underlayment, drip edge, step flashing, architectural shingles, beadboard/vinyl ceiling and trim, structural hardware

176

sqft

\$75.00

\$13,200.00

Covered porch — labor (22×8 ft, 176 sq ft): layout, footings and posts, deck framing and ledger, roof framing and sheathing, roofing install, composite deck and fascia, railing, column wraps, ceiling finish, permit coordination, inspections, supervision, site protection, and cleanup

176

sqft

\$70.00

\$12,320.00

Subtotal

\$25,520.00

Total

\$25,520.00

Scope of Work

Project overview

Furnish all labor, materials, and supervision to build a 22 ft × 8 ft (176 sq ft) covered porch

Work performed per applicable NH building codes and local amendments

Permits and inspections

Assist with building permit application and required drawings

Schedule inspections for footings, framing, roofing, and final as required by town

Foundation and posts

Install concrete footings below local frost depth for porch posts

Set (3) pressure-treated 6×6 posts plumb and to elevation

Install post bases, anchors, and approved hardware

Deck structure and framing

Attach ledger to existing structure with flashing and waterproofing at house connection

Install pressure-treated 2×10 beams, rim boards, blocking, and joists per span requirements

Install approved joist hangers, hurricane ties, and structural fasteners (not shown on material takeoff)

Roof structure

Frame roof with 2×10 headers, rafters, and 2×6 ceiling ties per plan

Install 1/2" roof sheathing and structural connections at house tie-in

Roofing

Install ice and water shield at eaves and critical transitions

Install synthetic underlayment over sheathing

Install drip edge, step flashing at house wall, and architectural shingles

Tie roof drainage into existing gutters only if specified in writing

Decking and rail

Install composite decking with hidden fasteners on framed deck surface

Install composite fascia at exposed edges

Install composite railing system at open sides per code (guard height and spacing)

Columns and ceiling

Install 6×6 column wrap kits at structural posts

Install beadboard or vinyl ceiling finish with J-channel and F-channel trim

Cleanup and closeout

Daily jobsite cleanup; haul off construction debris

Final walkthrough with homeowner

Provide care instructions for composite and roof finishes

Estimated timeline

Approximately 12 working days on site, weather permitting

Estimated Timeline

Approximately 12 working days on site (7 days reference for a 144 sq ft deck). Weather, permits, and material lead times may adjust start/finish.

Exclusions

Electrical wiring, panels, and fixtures (by licensed electrician unless added)

Plumbing, gas lines, and HVAC (by licensed trades unless added)

Interior paint, stain, and floor finishes unless explicitly listed

Landscaping, irrigation repair, and hardscape beyond disturbed areas

Engineering or architectural stamp if required by town (quoted separately)

Unforeseen site conditions (rock, ledge, poor soils) — change order if encountered

Notes

Questions? Call (978) 888-8068 or email rposull@hotmail.com. Deposit and payment schedule per signed contract. Permit fees included in materials allowance where noted by town.

Generated by OpenJarvis. This estimate is valid for 30 days.